KOLAR DIVISION.

Notice dated 31st January 1929.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M. of 25th February 1929, for restoring Singarahalli Hongekere, Serial No. 581 of Bowringpet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred, in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Restoring Singarahalli-Hongekere, Serial No. 581, Bowringpet Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for which item of work both in figures and words.

10. The tenderers stating that the work would be carried out at a certain percentage in excess or lower than the estimate will not be accepted.

Details abstract estimate of Singarahally-Hongekere of Bowringpet Taluk.

Items of work	Per	Rate			Quantity	Cost
Bund.		Rs.	a.	p.		Rs.
1. Removal of sand at breach site ...	C.yd.				253	
2. Cutting open bund at left of breach for imbedding the puddle wall.	Lump	sum			...	
3. Excavating foundation clayey soil ...	C.yd.				21	
4. Puddle wall	,,				106	
5. Earthwork to bund, watering and tamping including lead and left.	,,				2938	
6. Turfing to bund	Sqr.				2198	
7. Resetting old stone with new jelly ...	C.yd.				486	
8. New stone work	,,				295	
9. Fixing grade stones cutting figures painting and bed slab, etc.	Each				12	
10. Index stones do ...	,,				12	
11. Register No. Stone with bed slab do ..	,,				1	
12. B. M. Stones do do ...	,,				2	
13. Gauge stone do do ...	,,				1	
14. Jungle clearing with rools and cutting grips, etc.	Grade				9	
Total Bund ...	...	...	...	...	...	...

Items of work	Per	Rate	Quantity	Cost
Sluice R. L. 45·00.		Rs. a. p.		Rs.
Earthwork—				
1. Excavating earth	C.yd.		55	
2. Refilling with watering and tamping ...	,,		60	
3. Concrete in surki mortar	C.ft.		177	
4. Burnt brick in surki mortar	,,		421	
5. Burnt stone slabs 6" thick	S.ft.		146	
6. Boring hole in slabs	Lump	sum	..	
7. Plasting with surki mortar	Sqr.		3·68	
8. Cast iron pipe 5" diameter	R.ft.		27	
9. Plug and rod with locking arrangements ...	Lump	sum	...	
Total Sluice ...	...	... .	...	...
Weirs at R. L. 50·00.				
Left weir—				
1. Earthwork clearing site	C.yd.		462	
2. New stone work	,,		129	
3. Toe slabs	S.ft.		144	
4. Pin slabs 12'×1'	Each		14	
5. Concrete in surki granting	Lump	sum	...	
Total Left Weir ...	...	... ...	...	...
Right Weir—				
1. Clearing site	Lump	sum	...	
2. Excavating foundation bard chettu soil ...	C.yd.		45	
3. Chistling soft rock	Lump	sum	..	
4. Earthwork to flank	C.yd.		432	
5. New stone work	,,		91	
6. Burnt stone slabs	S.ft.		72	
7. Pin slabs	Each		6	
8. Surki concrete granting	Lump	sum	...	
Total Right Weire ...	...	.. ..	...	..
Total of bund, sluice and weir contingencies at 5 per cent.	...	... ...	...	...
Grand Total ...	...	... ...	...	...

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Notice dated 31st January 1929.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 18th February 1929, for constructing a District Board Office Building at Tumkur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.